

The unresolved hard X-ray background: the missing source population implied by the *Chandra* and *XMM-Newton* deep fields

M. A. Worsley,^{1*} A. C. Fabian,¹ F. E. Bauer,¹ D. M. Alexander,¹
G. Hasinger,² S. Mateos,³ H. Brunner,² W. N. Brandt⁴ and D. P. Schneider⁴

¹*Institute of Astronomy, Madingley Road, Cambridge CB3 0HA*

²*Max-Planck-Institut für extraterrestrische Physik, Postfach 1319, D-85740 Garching, Germany*

³*Instituto de Física de Cantabria (CSIC-UC), 39005 Santander, Spain*

⁴*Department of Astronomy and Astrophysics, 525 Davey Laboratory, Pennsylvania State University, University Park, PA 16802, USA*

2 February 2008

ABSTRACT

We extend our earlier work on X-ray source stacking in the deep *XMM-Newton* observation of the Lockman Hole, to the 2 Ms *Chandra* Deep Field North and the 1 Ms *Chandra* Deep Field South. The *XMM-Newton* work showed the resolved fraction of the X-ray background to be ~ 80 –100 per cent at $\lesssim 2$ keV but this decreased to only ~ 50 per cent above ~ 8 keV. The CDF-N and CDF-S probe deeper, and are able to fill-in some of the missing fraction in the 4–6 keV range, but the resolved fraction in the 6–8 keV band remains only ~ 60 per cent, confirming the trend seen with *XMM-Newton*. The missing X-ray background component has a spectral shape that is consistent with a population of highly obscured AGN at redshifts ~ 0.5 –1.5 and with absorption column densities of $\sim 10^{23}$ – 10^{24} cm $^{-2}$.

Key words: surveys – galaxies: active – cosmology: diffuse radiation – X-rays: galaxies – X-rays: diffuse background

1 INTRODUCTION

The nature of the X-ray background (XRB) has been a subject of contention since its discovery 40 years ago (Giacconi et al. 1962). It is now clear that at energies above ~ 1 keV the background is made up of the summed emission from point sources, principally Active Galactic Nuclei (AGN). The spectrum measured by the HEAO satellite (Marshall et al. 1980) is similar in shape to 40 keV bremsstrahlung and is well-described by a $\Gamma = 1.4$ power-law from ~ 1 up to ~ 15 keV where it starts to flatten off before peaking in νI_ν at ~ 30 keV. Below ~ 1 keV the background is dominated by diffuse Galactic and local bubble emission; the purely extragalactic component has not been well determined.

Resolving the XRB into discrete sources is crucial to understanding the nature of the AGN and galaxy populations in the Universe. It also allows us to place limits on the residual XRB emission which can be attributed to other processes, including that from truly diffuse extragalactic emission. A significant amount (~ 70 –80 per cent) of the 0.5–2 keV XRB was resolved into point sources by ROSAT (Hasinger et al. 1998) but progress at harder energies has required the improved sensitivity and spatial resolution of the *Chandra* and *XMM-Newton* observatories. *XMM-Newton* was able to resolve some ~ 60 per cent of the 5–10 keV back-

ground in a deep survey of the Lockman Hole, reaching a limiting flux of $\sim 3 \times 10^{-15}$ erg cm $^{-2}$ s $^{-1}$ in this band (Hasinger et al. 2001). The *Chandra* Deep Fields North and South probe down to ~ 1.4 – 2.8×10^{-16} erg cm $^{-2}$ s $^{-1}$ (over 2–8 keV) and resolve ~ 70 –90 per cent of the background in this broad, hard band (Giacconi et al. 2002; Moretti et al. 2002; Alexander et al. 2003; and references therein).

The large resolved fractions found in the deep surveys appear to solve the problem of the origin of the XRB in terms of known sources; an extrapolation of the 0.5–2 keV band $\log N$ – $\log S$ distribution points to an integrated flux consistent with the full XRB level. The substantial resolved fraction in the broad 2–10 keV band is not entirely consistent with this picture; a similar extrapolation of the 2–10 keV $\log N$ – $\log S$ distribution is, at most, only able to account for some 93 per cent of the total XRB and is only marginally consistent with complete resolution (Moretti et al. 2003). The most recent XRB intensity measurement by De Luca & Molendi (2004) would make the fraction only ~ 80 per cent.

To investigate in detail the resolved XRB fraction as a function of energy, Worsley et al. (2004) carried out a source-stacking analysis of ~ 700 ks of accumulated *XMM-Newton* exposure in the Lockman Hole. Source photometry was used to determine the resolved fraction in a number of narrow energy bands from 0.2 to 12 keV. The authors found the resolved fraction to be $\gtrsim 80$ per cent below 2 keV but that this decreased significantly at higher en-

* E-mail: maw@ast.cam.ac.uk

ergies, falling to only ~ 50 per cent above ~ 8 keV. The failure to account for XRB in the harder bands, along with recent indications of steepening of X-ray source number counts at low fluxes, suggest that there may be an as-yet undetected population of highly obscured sources, such as the heavily absorbed AGN predicted in recent synthesis models (e.g. Gilli et al. 2001; Franceschini et al. 2002; Gandhi & Fabian 2003; Ueda et al. 2003; Comastri 2004).

Although *Chandra* has low effective area at energies exceeding 7 keV, the *Chandra* Deep Fields (CDFs) probe to fainter flux limits than the *XMM-Newton* Lockman Hole observation. We use the CDFs to assess whether the contribution of the fainter sources found by *Chandra* are able to resolve the discrepancy and account for the missing background fraction. Using a similar photometric analysis we sum the flux from resolved CDF sources in a number of narrow energy bands to determine the resolved fraction of the X-ray background. We also present a re-analysis of the *XMM-Newton* Lockman Hole observation (Worsley et al. 2004), carried out in identical energy bands for direct comparison with the CDFs. In both cases we attempt to quantify and correct for field-to-field variations and the missing flux which would arise from the very bright sources which are not sampled in these deep, pencil-beam surveys.

2 SOURCE DETECTION AND PHOTOMETRY

2.1 Chandra Deep Field Observations

Chandra has performed the two deepest ever surveys of the X-ray universe – the 2 Ms *Chandra* Deep Field North (CDF-N; Alexander et al. 2003) and the 1 Ms *Chandra* Deep Field South (CDF-S; Giacconi et al. 2002). The CDF-N probes down to $\sim 2.5 \times 10^{-17}$ and $\sim 1.4 \times 10^{-16}$ erg cm $^{-2}$ s $^{-1}$ in the 0.5–2 and 2–8 keV bands respectively. Although the CDF-S only reaches down to equivalent limits (at $S/N = 3$) of $\sim 5.2 \times 10^{-17}$ and $\sim 2.8 \times 10^{-16}$ erg cm $^{-2}$ s $^{-1}$, these are both well beyond the 10^{-14} erg cm $^{-2}$ s $^{-1}$ break in the log N –log S distribution (see e.g. Hasinger et al. 1998; Campana et al. 2001).

For both the CDF-N and CDF-S we use the source catalogues and photometry from Alexander et al. (2003), who describe their approach thoroughly; we include a brief summary here for completeness. The 2 Ms CDF-N main point-source catalogue contains a total of 503 sources and covers a total solid angle of 447.8 arcmin 2 . Conservative estimates place the number of falsely detected sources to be as high as 20–30 but the true number is probably considerably lower (see section 2.3 in Alexander et al. 2003). The CDF-S has 326 sources from a total field of 391.3 arcmin 2 .

The local background estimate for each source was determined in an annulus surrounding the source-extraction region. The mean number of background counts was computed assuming a Poisson distribution, as n_1/n_0 ; where n_1 is the number of pixels containing a single count and n_0 is the number containing no counts. For sources with less than 10^3 counts in the full 0.5–8 keV band, source-extraction apertures containing 90–95 per cent of the encircled energy fraction (EEF) were chosen (with the extracted counts corrected up to 100 per cent). For sources brighter than 10^3 counts, extraction apertures of twice this size were chosen; the EEF in these cases is close to 100 per cent. The EEF corrections used to correct from aperture counts to total counts were calculated from the *Chandra* point spread function (PSF) determined using the *Chandra* X-ray Centre MKPSF software (refer to Alexander et al. 2003).

For all sources with a sufficient number of counts, the ratio of counts between the 2–8 keV and 0.5–2 keV bands was used to determine an effective spectral index for a power-law model, allowing for Galactic absorption of $(1.3 \pm 0.4) \times 10^{20}$ and $(8.8 \pm 4.0) \times 10^{19}$ cm $^{-2}$ for the CDF-N and CDF-S respectively (Lockman 2003; Stark et al. 1992). For sources with an insufficient number of counts, the photon index is fixed at $\Gamma = 1.4$ (the approximate average for all the sources and the slope of the XRB). The flux for each source was calculated in a number of photometric bands, regardless of whether or not the source is actually detected in each of the bands. In each case the counts-to-flux conversion is appropriate to the spectral index of the source. The photometric bands used were 0.5–1, 1–2, 2–4, 4–6 and 6–8 keV.

Prior to our stacking analysis (described in section 3.1), we applied the systematic flux correction determined by Bauer et al. (2004) for both the CDFs (see section 3 and Fig. 2 of their paper). These take into account Eddington bias as well as some further aperture/photometry effects that were not considered originally. The correction is negligible except in the harder (> 2 keV) bands which each see an increase in total resolved flux of ~ 2 –5 per cent.

2.2 XMM-Newton Lockman Hole Observations

XMM-Newton, whilst unable to match the X-ray resolution and ultimate sensitivity of *Chandra*, has the critical advantage of sensitivity in the 8–12 keV regime. It was this capability, put into effect with ~ 700 ks of deep observations in the Lockman Hole (XMM-LH), that prompted Worsley et al. (2004) to investigate the resolved fraction of the XRB with energy.

The 17 different individual observations that comprise the XMM-LH were combined and source detection carried out using sliding-box detection followed by maximum-likelihood PSF fitting. Visual inspection of the source candidates was used to exclude spurious detections. The analysis was restricted to the central 314.2 arcmin 2 region of the field with the highest exposure time and lowest background level.

In a similar approach to that taken in the CDFs, simple aperture photometry was performed on the exposure-corrected images in a number of narrow energy bands. A more detailed description of the following is given by Worsley et al. (2004). For each source, the total count-rates were extracted in both a circular aperture and a surrounding annulus. These were then used to calculate the background-corrected source count rate, taking into account corrections for the EEF. These corrections were calculated by integrating an analytical model of the *XMM-Newton* PSF given in *XMM-Newton* Science Operations Centre calibration documents (refer to Worsley et al. 2004). Count-rate extraction apertures/annuli were chosen to the maximise the signal-to-noise ratio.

Count-rate-to-flux conversion factors were computed assuming a fixed spectral slope of $\Gamma = 1.4$ and Galactic absorption with a column density of 5×10^{19} cm $^{-2}$ (Lockman et al. 1986). This is not as rigorous as the approach taken in the CDFs where counts-to-flux conversion factors (ECFs) appropriate to the spectral slope of the source were used, but the larger count rate errors for the *XMM-Newton* sources prohibit this, and the assumption of a fixed $\Gamma = 1.4$ is more reliable. Furthermore, the dependence of the ECFs on the spectral shape of a source is only weak because of the use of narrow energy bands. The ECFs of all but the 0.2–0.5 keV band vary by $\lesssim 5$ per cent over the range $\Gamma = 0.9$ –1.9 (the 0.2–0.5 keV band has a ~ 15 per cent variation). The resultant uncertainty in the resolved total flux from the source population is small in comparison with other errors.

Table 1. Parameters used in the XMM-LH photometric analysis. For each energy band the cut-out radii are quoted: r_1 is the radius of the source count-rate extraction aperture; r_2 and r_3 are the inner and out radii of the background count-rate extraction annulus; refer to sections 2.3-2.4 and Fig. 1 in Worsley et al. (2004) for further details. Also quoted are the count-rate to flux energy conversion factors calculated for each band following the method described in section 2.5 of that paper.

Energy band (keV)	Cut-out radii (arcsec)						Weighted energy conversion factors (10^{11} count $\text{cm}^2 \text{erg}^{-1}$)		
	PN			MOS			PN	MOS-1	MOS-2
0.2–0.5	14	30	40	12	25	35	7.052	1.263	1.242
0.5–1	15	30	40	13	25	35	7.375	1.757	1.735
1–2	14	30	40	12	25	35	5.631	1.994	1.977
2–4	11	30	40	10	25	35	1.960	0.7650	0.7664
4–6	10	25	35	8	25	35	1.143	0.4017	0.4207
6–8	8	20	30	6	20	30	0.6694	0.1347	0.1411
8–12	6	15	25	5	15	25	0.1908	0.02059	0.02220

In order to allow easy comparison with the *Chandra* data, the XMM-LH analysis was repeated using the same energy bands as in the CDFs with additional bands covering 0.2–0.5 and 8–12 keV. The re-processing of the data took advantage of the latest releases of the *XMM-Newton* SCIENCE ANALYSIS SYSTEM (SAS) v6.0.0 and the X-ray spectral analysis package XSPEC v11.3.1. Additionally, rather than use the original source list (from Worsley et al. 2004), of 126 objects, we took advantage of the complete – and more rigorously compiled – Lockman Hole source catalogue of Mateos et al. (in prep.), which contains 156 sources in the same 314.2 arcmin^2 region. Table 1 gives the values of various important parameters used in the re-processing of the data.

3 RESULTS

3.1 Resolving the X-ray background

The total resolved flux in each energy band was calculated by summing the measured flux for each source. Every source is included regardless of whether or not it is detected in the band. This was done for the CDF-N, CDF-S and each of the three *XMM-Newton* instruments in the XMM-LH. Appropriate corrections for Galactic absorption were made. These correction factors are 15 per cent in the XMM-LH 0.2–0.5 keV band; 2.6, 7.2 and 4.8 per cent in the 0.5–1 keV band for the XMM-LH, CDF-N and CDF-S respectively; and $\lesssim 1$ per cent for all of the harder bands.

In order to calculate the resolved intensity, the flux from each source must be divided by a solid angle on the sky. In the case of the XMM-LH the sensitivity is approximately constant over the region considered here and we simply take the solid angle to be a constant 314.1 arcmin^2 . The CDFs, however, show a substantial increase in sensitivity towards the centre of the fields. The total solid angles of 447.8 and 391.3 arcmin^2 are only applicable to the brightest sources, whereas fainter sources are only detectable over a fraction of the field and the actual solid angles are smaller. Fig. 19 in Alexander et al. (2003) shows the solid angle as a function of 0.5–8 keV source flux in the CDF-N. We use this function (and its equivalent for the CDF-S) to provide the appropriate solid angle when converting each source flux to an intensity. We impose a minimum effective area of 10 per cent of the total to avoid catastrophically magnifying the errors in the fluxes from the faintest sources.

Fig. 1(a) shows the resolved XRB fraction obtained in each energy band. The fractions are calculated using the most recent estimates of the total extragalactic XRB spectrum. For the 1–8 keV band this is the power-law model of De Luca & Molendi




Figure 1. The fraction of the total extragalactic XRB intensity resolved by simply summing the fluxes of sources in the CDFs and XMM-LH. CDF-N and CDF-S data are shown as the black and grey crosses respectively; XMM-LH PN camera data are shown as dashed diamonds and both the MOS-1 and MOS-2 camera data are both shown using dotted diamonds. The three panels show; (a) the result of summing all sources, (b) the result of excluding sources brighter than $5 \times 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1}$ in 0.5–8 keV flux, and (c) the result of additionally excluding sources fainter than $10^{-16} \text{ erg cm}^{-2} \text{ s}^{-1}$ in 0.5–8 keV flux.

(2004), with a spectral slope of $\Gamma = 1.41$ and 1 keV normalisation of $11.6 \text{ keV cm}^{-2} \text{ s}^{-1} \text{ sr}^{-1} \text{ keV}^{-1}$. Above 8 keV the background spectrum starts to turn over slightly and so here we use the analytical model of Gruber et al. (1999) – which takes the downturn into account – but renormalised to the same 2–8 keV XRB flux as found by De Luca & Molendi (2004). The spectrum of the purely extragalactic background is not well constrained below 1 keV since it is difficult to separate from the bright, diffuse, Galactic component. There is evidence to suggest that the spectrum of the background steepens below $\sim 1 \text{ keV}$; Roberts & Warwick (2001) have combined the results of several X-ray shadowing measurements and report a background intensity of $26.6 \pm 4.8 \text{ keV cm}^{-2} \text{ s}^{-1} \text{ sr}^{-1} \text{ keV}^{-1}$ at 0.25 keV. A power-law fit between this value and the De Luca & Molendi (2004) intensity at 1 keV gives a spectral slope of $\Gamma \sim 1.5\text{--}1.7$ and we use this to estimate the background levels in the 0.2–0.5 and 0.5–1 keV bands.

The stacking of source fluxes reveals a decline in the resolved XRB fraction as a function of energy. Below $\sim 2 \text{ keV}$ the data diverge somewhat, presumably due to field-to-field variations. Such variations arise through the cosmic variance in the actual XRB normalisation in different regions of the sky, along with the statistical noise which is a consequence of sampling a discrete population of sources in a small solid angle. Fig. 1(b) shows the result of excluding sources with a 0.5–8 keV band flux $> 5 \times 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1}$ from the sum. While only a small number of sources have been removed (from 3–7 out of 156–503) the variation at the softest energies has been reduced considerably. This demonstrates that a large amount of the variation $< 2 \text{ keV}$ is due to soft, bright sources. The XMM-LH data now show a slight decline in the resolved fraction whilst the CDFs show a slight rise, although both CDFs show significant drops in the 6–8 keV band. This difference between the *XMM-Newton* and *Chandra* fractions in the 4–6 keV band is due to sensitivity – the CDFs probe down to fainter fluxes where the typical source spectrum is harder than $\Gamma = 1.4$ (see e.g. Alexander et al. 2003; Streblyanska et al. 2003). If the source lists are further restricted to remove the faint sources seen only by *Chandra*, with a minimum flux requirement of $10^{-16} \text{ erg cm}^{-2} \text{ s}^{-1}$, then the spectral shapes of the sources are similar for both XMM-LH and CDF, see Fig. 1(c). Of course, there will always remain differences between data-sets – Barcons et al. (2000) estimate the cosmic variation in XRB normalisation to be of order ~ 10 per cent for fields of $\lesssim 1 \text{ deg}^2$.

3.2 Correcting for the bright-end population

The brightest sources in the catalogues have 0.5–8 keV fluxes up to $\sim (1\text{--}3) \times 10^{-13} \text{ erg cm}^{-2} \text{ s}^{-1}$. There is a non-negligible contribution to the whole-sky background by sources brighter than this; in fact, around 15–20 per cent of the total XRB is due to bright, rare sources that are not sampled in pencil-beam surveys. A ‘bright-end correction’ is necessary to recover this missing intensity.

In order to remove some of the bright-end variation we truncate the source lists above $5 \times 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1}$ (0.5–8 keV band). This is the same truncation as used in Fig. 1(b) and corresponds to removing sources that only occur with densities of $\sim$ a few in the $\sim 0.1 \text{ deg}^2$ CDF and XMM-LH fields. With the bright-end sources removed the expected missing flux can be estimated by integrating known $\log N\text{--}\log S$ distributions. These are available in the broad 0.5–2 and 2–10 keV bands but not in the narrow bands used in this work. In order to calculate the contribution in a narrow band it is necessary to assume the spectral shape of

the sources. Here we assume a power-law spectrum but the typical spectral slope of such a power-law can be a strong function of source flux.

A number of studies point to significant evolution of the spectral shape with flux (Ueda et al. 1999; Fiore et al. 2003; Alexander et al. 2003; Streblyanska et al. 2003), with sources brighter than $\sim 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1}$ having typical spectral slopes much softer than the $\Gamma = 1.4$ of the total background. Shallow surveys (Ueda et al. 1999, see e.g.) find that the brightest sources, with X-ray fluxes $\gtrsim 10^{-13} \text{ erg cm}^{-2} \text{ s}^{-1}$, have spectral slopes of $\Gamma \sim 1.8\text{--}2.2$. Streblyanska et al. (2003) fitted a power-law spectrum to the stacked spectra of sources of a 500 ks *XMM-Newton* observation in the CDF-S. Fitting the hard band (1–8 keV) with a power-law reveals a strong correlation between spectral slope and flux, with $\Gamma \sim 1.8$ for $\sim 10^{-13} \text{ erg cm}^{-2} \text{ s}^{-1}$ (2–10 keV flux) decreasing to $\Gamma \sim 1.5$ at $\sim 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1}$ and $\Gamma \sim 1.2$ at $\sim 10^{-15} \text{ erg cm}^{-2} \text{ s}^{-1}$. Alexander et al. (2003) see sources with $\Gamma \sim 1$ at fluxes $\lesssim 10^{-16} \text{ erg cm}^{-2} \text{ s}^{-1}$ in the CDF-N.

We have taken a linear fit to the evolution of spectral index with flux based on the relationship as observed by Streblyanska et al. (2003), although we conservatively impose a maximum value of $\Gamma = 2$. Such a model is only an approximation to the actual dependence of spectral shape with flux. It does, however, follow the trends observed by Streblyanska et al. (2003) in the CDF-S (using both *XMM-Newton* and *Chandra* observations) and Ueda et al. (1999) using the ASCA Medium-Sensitivity Survey, and whilst crude, it is important to take into account the fact that the bright-end correction is due to sources which are significantly softer than those which we have already stacked. Given our model, the bright-source contribution in each of the 2–4, 4–6, 6–8 and 8–12 keV narrow bands can then be calculated, using an appropriate spectral index at each source flux, from the 2–10 keV flux contribution obtained by integrating the Moretti et al. (2003) hard band $\log N\text{--}\log S$ distribution (the most complete published to date).

Correcting the soft bands (0.2–0.5, 0.5–1 and 1–2 keV) is more complex, since the shape of the background is not well constrained. The source stacking approach of Streblyanska et al. (2003) in the 0.4–8 keV range revealed a systematically softer spectrum than that seen for 1–8 keV (an increase in Γ of ~ 0.1). No studies cover the 0.5–2 keV range ideally required for the soft band bright-end correction so we take the same linear fit to the evolution of spectral index as used in the hard band, but with an increase in Γ by 0.1. We use the Moretti et al. (2003) 0.5–2 keV soft band $\log N\text{--}\log S$ distribution. There is now some evidence to suggest that the Moretti et al. (2003) $\log N\text{--}\log S$ slope is too steep at the bright end compared to results from the RIXOS, RBS and NEPS surveys (Mason et al. 2000; Schwoppe et al. 2000; Gioia et al. 2003); thus, our bright-end correction in the soft band could potentially be an underestimate.

Fig. 2 shows the bright-end corrected resolved background fractions. The XMM-LH, CDF-S and CDF-N are all consistent with a similar resolved fraction of $\sim 70\text{--}90$ per cent up to $\sim 4 \text{ keV}$. The differences are of order ~ 10 per cent which is not inconsistent with what would be expected from cosmic variance between the fields (see Barcons et al. 2000). *XMM-Newton* sees a drop in the resolved fraction in the 4–6 keV band whereas the CDFs are still consistent with a high resolved fraction of $\sim 80\text{--}90$ per cent. This difference is due to the faint, hard sources which are not detected in the XMM-LH; if these sources are removed from the *Chandra* data then all three data-sets show agreement in the 4–6 keV fraction.

Most importantly, the picture is different at high energies; *XMM-Newton* and both *Chandra* deep fields only resolve ~ 50 – 70 per cent of the background in the 6–8 keV band, much less than the fraction at lower energies. The 8–12 keV band, as probed by *XMM-Newton*, is only ~ 40 – 60 per cent resolved.

We find the total resolved fluxes in the 0.5–2 and 2–8 keV bands to be $(6.9 \pm 0.2) \times 10^{-12}$ and $(1.5 \pm 0.1) \times 10^{-11} \text{ erg cm}^{-2} \text{ s}^{-1}$ for the CDF-N. These compare well with the $(6.7 \pm 0.3) \times 10^{-12}$ and $(1.66 \pm 0.05) \times 10^{-11} \text{ erg cm}^{-2} \text{ s}^{-1}$ reported in Bauer et al. (2004) from a detailed analysis of the combined CDF number counts. The fluxes can also be compared to the $(7.1 \pm 0.3) \times 10^{-12}$ and $(1.43 \pm 0.08) \times 10^{-11} \text{ erg cm}^{-2} \text{ s}^{-1}$ determined integrating the log N –log S curves of Moretti et al. (2003) (although note that these do not contain the 2 Ms extension to the original 1 Ms CDF-N).

We find the total 0.5–2 and 2–8 keV resolved fractions are ~ 85 and ~ 80 per cent for the CDF-N (using the total XRB spectrum we describe in section 3.1). Such high fractions are often used to claim that the XRB is almost completely resolved into discrete sources even in the broad 2–10 keV band. Our results suggest that stating a resolved fraction in this manner is misleading, since it is the high resolved fractions in the 2–6 keV range which are dominating the total, whilst the resolved fraction beyond 6 keV is significantly lower.

4 DISCUSSION

Three independent observations now point to a significant reduction in the resolved fraction of the X-ray background at the hardest energies. *XMM-Newton* starts to see a downturn above ~ 4 keV whilst *Chandra* is sensitive to the fainter, harder sources, which fill in some of the missing fraction and push the downturn to energies $\gtrsim 6$ keV. The missing fraction has the spectral signature of highly obscured AGN and could be evidence of the large population of heavily absorbed objects which are thought to account for the 30 keV peak of XRB intensity (see e.g. Maiolino et al. 1998, 2003).

To quantify the possible nature of an undetected population, we modelled the spectral shape of the unresolved background as a function of redshift and intrinsic absorption column density. A grid of spectra was built in the range $z = 0.1$ – 3 and $N_{\text{H}} = 10^{22}$ – 10^{25} cm^{-2} . XSPEC v11.3.1 was used to generate the spectra using a PEXRAV model (Magdziarz & Zdziarski 1995), with a $\Gamma = 2$ power-law and an $R = 1$ reflection component (see e.g. Malizia et al. 2003), multiplied by ZWABS (Morrison & McCammon 1983) photoelectric absorption at the source redshift.

We computed the goodness-of-fit between each model spectrum and the residual XRB spectrum (i.e. the difference between the resolved and total backgrounds). Fig. 3 shows the confidence contours in the redshift and absorption column density required to account for the shape of the missing AGN population for the XMM-LH. This is a rather simplistic approximation to the spectra of highly obscured sources; specifically, we neglect the effects of iron K emission and scattered-flux components, as well as assuming that the missing sources occur at a fixed redshift and with a fixed absorption column density. Nevertheless, some generalised conclusions about the nature of the unresolved population can be drawn.

The XMM-LH, CDF-N and CDF-S all show similar contour




Figure 2. The upper panel shows the total extragalactic XRB (thick black crosses) along with the intensity resolved into sources in the CDF-N (black crosses), CDF-S (grey crosses) and combined PN/MOS-1/MOS-2 results in the XMM-LH (black diamonds). The resolved intensities have been corrected for the bright-end population by removing all sources with 0.5–8 keV flux $> 5 \times 10^{-14} \text{ erg cm}^{-2} \text{ s}^{-1}$ and then adding the missing flux from sources brighter than this by integrating log N –log S distributions (refer to section 3.2). The lower panel shows the resolved intensities as fractions of the total extragalactic XRB in each energy band.

diagrams for the characteristics of the missing source population. The XMM-LH data, which extends to the 8–12 keV band, shows the most constrained set of contours although the degeneracy between low- z /low- N_{H} and high- z /high- N_{H} is clear. The best-fitting point is at $z \sim 0.8$ and $N_{\text{H}} \sim 4.5 \times 10^{23} \text{ cm}^{-2}$. For the CDF-N and CDF-S the lack of data above 8 keV results in much more relaxed contours although there is again some preference for sources at $z \sim 0.5$ – 1.5 with $N_{\text{H}} \sim 10^{23}$ – 10^{24} cm^{-2} . Figure 4 shows the total and resolved levels of the XRB in νI_{ν} as well as the intensity that would be contributed by the best-fitting model of an obscured population.

We conclude that whilst the data are unable to constrain tightly the spectral shape of the missing XRB sources, the most plausible population would seem be of objects at redshifts of ~ 0.5 – 1.5 , with unabsorbed luminosities of $\lesssim 5 \times 10^{43} \text{ erg s}^{-1}$, but heavily obscured by column densities of $\sim 10^{23}$ – 10^{24} cm^{-2} . The CDFs probe deeper than the XMM-LH but still fail to detect the missing sources in the 2–4 keV band, or our stacking analysis would have revealed the higher energy emission. Any soft starburst or scattered emission in these objects must be small and this may suggest a high covering fraction for the absorption.




Figure 3. Contour plot of fits to the spectral shape of the missing XRB spectrum for the XMM-LH data in the 2–12 keV range. 68, 90 and 95 per cent confidence contours are shown. The best-fitting point is indicated at $z \sim 0.8$ and $N_{\text{H}} \sim 4.5 \times 10^{23} \text{ cm}^{-2}$. The grey contours indicate the maximum, unobscured, rest-frame 2–10 keV luminosity (erg s^{-1}) of the source population required such that the sources remain below the sensitivity limit (estimated at $\sim 1.5 \times 10^{-15} \text{ erg cm}^{-2} \text{ s}^{-1}$ in a 4–8 keV band).

In order to provide the missing fraction of the hard X-ray background these sources must have a density on the sky of $> 2800 \text{ deg}^{-2}$. This would correspond to a lower limit of around 350 undetected AGN in the CDF-N. There must therefore be > 3 times more undetected, obscured sources than detected, unobscured ones, in the 4–8 keV band. This requires that the sources in the new population have a high covering fraction of obscuring matter.

From the absorption-corrected flux we can estimate the black hole mass density of this obscured population to be $(6\text{--}9 \times 10^4) \epsilon_{-1}^{-1} \kappa_{-1} \text{ M}_{\odot} \text{ Mpc}^{-3}$; where ϵ_{-1} is the accretion efficiency in units of 0.1 and κ_{-1} is a bolometric correction in units of 0.1. We have used a similar calculation to Fabian & Iwasawa (1999) although note that the bolometric correction is $\sim 10\text{--}15$ for our lower-luminosity (Fabian 2004). The missing population thus accounts for $\sim 10\text{--}20$ per cent of the local black hole mass density of $4\text{--}5 \times 10^5 \text{ M}_{\odot} \text{ Mpc}^{-3}$ (see e.g. Shankar et al. 2004), the rest of which is due to bright AGN and, in particular, quasars, where the bolometric correction is ~ 30 or more, and where a typical redshift of $z \sim 2$ is more appropriate (refer to Fabian & Iwasawa 1999 and references therein).

The steepness of the 5–10 keV source number counts, with no evidence for a break to a flatter slope at the faint end, also indicates that there remains a substantial number of objects which have yet to be found in this band (Hasinger et al. 2001; Rosati et al. 2002; Baldi et al. 2002). Recent optical and infra-red data from the HST and Spitzer telescopes, acquired as part of the GOODS project, are also providing evidence for large numbers of obscured AGN at $z > 1$ (e.g. Treister et al. 2004). Deep, multi-wavelength efforts such as GOODS may well be the best way to identify the missing population; confirmation of Compton-thick objects will ultimately require X-ray missions with high sensitivities beyond 10 keV, such as the next generation of focusing hard X-ray telescopes.

5 CONCLUSIONS

- Whilst the XRB is ~ 85 and ~ 80 per cent resolved in the broad 0.5–2 and 2–10 keV bands respectively (depending on XRB




Figure 4. The upper curve shows the total extragalactic XRB (as described in section 3.1) in νI_{ν} . The intensity resolved into sources in the CDF-N, CDF-S and XMM-LH are shown as black crosses, grey crosses and black diamonds respectively. The lower curve shows the spectrum of the best-fitting model for the missing AGN population with $z = 0.8$ and $N_{\text{H}} = 4.5 \times 10^{23} \text{ cm}^{-2}$. Sharp features (such as that due to iron at 4 keV), is a consequence of our assumption that the missing population is composed entirely of AGN with this spectrum. In reality the missing population will be mixture of sources at different redshifts and with different levels of absorption; any sharp features will be smeared-out.

normalisation), it is only ~ 60 per cent resolved above ~ 6 keV and ~ 50 per cent resolved above ~ 8 keV. This decrease in resolved fraction is seen in both the CDFs and the XMM-LH.

- The decrease in resolved fraction as seen in XMM-LH occurs at energies $\gtrsim 4$ keV whilst in the CDFs the drop occurs at $\gtrsim 6$ keV. This difference is due to faint, hard sources which are detected in CDFs but not the XMM-LH. All three surveys are unable to account for almost half of the X-ray background above ~ 6 keV.

- The missing fraction has a spectral shape that is consistent with that which would be expected from a population of faint, heavily obscured AGN located at a redshift of $\sim 0.5\text{--}1.5$ and with intrinsic absorption columns of $\sim 10^{23}\text{--}10^{24} \text{ cm}^{-2}$.

- The deep CDF data show that any such obscured population is not detected in the 2–4 keV band, or our stacking analysis would have revealed the higher energy emission; consequently, any soft scattered or starburst emission from these objects must be small.

6 ACKNOWLEDGMENTS

Based on observations with *XMM-Newton*, an ESA science mission with instruments and contributions directly funded by ESA Member States and the USA (NASA). MAW and FEB acknowledge support from PPARC. ACF and DMA thank the Royal Society for support. WNB thanks the CXC grant GO2-31287A. We would also like to thank the anonymous referee for help comments.

REFERENCES

- Alexander D. M. et al., 2003, *AJ*, 126, 539
- Baldi A., Molendi S., Comastri A., Fiore F., Matt G., Vignali C., 2002, *ApJ*, 564, 190
- Barcons X., Mateos S., Ceballos M. T., 2000, *MNRAS*, 316, L13

- Bauer F. E., Alexander D. M., Brandt W. N., Schneider D. P., Treister E., Hornschemeier A. E., Garmire G. P., 2004, *AJ*, 128, 2048
- Campana S., Moretti A., Lazzati D., Tagliaferri G., 2001, *ApJ*, 560, L19
- Comastri A., 2004 (astro-ph/0406031)
- De Luca A., Molendi S., 2004, *A&A*, 419, 837
- Fabian A. C., 2004, in *Coevolution of Black Holes and Galaxies*, p. 447
- Fabian A. C., Iwasawa K., 1999, *MNRAS*, 303, L34
- Fiore F. et al., 2003, *A&A*, 409, 79
- Franceschini A., Braito V., Fadda D., 2002, *MNRAS*, 335, L51
- Gandhi P., Fabian A. C., 2003, *MNRAS*, 339, 1095
- Giacconi R., Gursky H., Paolini F. R., Rossi B. B., 1962, *Physical Review Letters*, 9, 439
- Giacconi R. et al., 2002, *ApJS*, 139, 369
- Gilli R., Salvati M., Hasinger G., 2001, *A&A*, 366, 407
- Gioia I. M., Henry J. P., Mullis C. R., Böhringer H., Briel U. G., Voges W., Huchra J. P., 2003, *ApJS*, 149, 29
- Gruber D. E., Matteson J. L., Peterson L. E., Jung G. V., 1999, *ApJ*, 520, 124
- Hasinger G. et al., 2001, *A&A*, 365, L45
- Hasinger G., Burg R., Giacconi R., Schmidt M., Trumper J., Zamorani G., 1998, *A&A*, 329, 482
- Lockman F. J., 2003 (astro-ph/0311386)
- Lockman F. J., Jahoda K., McCammon D., 1986, *ApJ*, 302, 432
- Magdziarz P., Zdziarski A. A., 1995, *MNRAS*, 273, 837
- Maiolino R. et al., 2003, *MNRAS*, 344, L59
- Maiolino R., Salvati M., Bassani L., Dadina M., della Ceca R., Matt G., Risaliti G., Zamorani G., 1998, *A&A*, 338, 781
- Malizia A., Bassani L., Stephen J. B., Di Cocco G., Fiore F., Dean A. J., 2003, *ApJ*, 589, L17
- Marshall F. E., Boldt E. A., Holt S. S., Miller R. B., Mushotzky R. F., Rose L. A., Rothschild R. E., Serlemitsos P. J., 1980, *ApJ*, 235, 4
- Mason K. O. et al., 2000, *MNRAS*, 311, 456
- Moretti A., Campana S., Lazzati D., Tagliaferri G., 2003, *ApJ*, 588, 696
- Moretti A., Lazzati D., Campana S., Tagliaferri G., 2002, *ApJ*, 570, 502
- Morrison R., McCammon D., 1983, *ApJ*, 270, 119
- Roberts T. P., Warwick R. S., 2001, in *ASP Conf. Ser. 234: X-ray Astronomy 2000*, p. 569
- Rosati P. et al., 2002, *ApJ*, 566, 667
- Schwöpe A. et al., 2000, *Astronomische Nachrichten*, 321, 1
- Shankar F., Salucci P., Granato G. L., De Zotti G., Danese L., 2004, *MNRAS*, 387
- Stark A. A., Gammie C. F., Wilson R. W., Bally J., Linke R. A., Heiles C., Hurwitz M., 1992, *ApJS*, 79, 77
- Streblyanska A., Bergeron J., Brunner H., Finoguenov A., Hasinger G., Mainieri V., 2003 (astro-ph/0309089)
- Treister E. et al., 2004, *ApJ*, 616, 123
- Ueda Y., Akiyama M., Ohta K., Miyaji T., 2003, *ApJ*, 598, 886
- Ueda Y., Takahashi T., Ishisaki Y., Ohashi T., Makishima K., 1999, *ApJ*, 524, L11
- Worsley M. A., Fabian A. C., Barcons X., Mateos S., Hasinger G., Brunner H., 2004, *MNRAS*, 352, L28